MODEL AH-1
Schematic

A. H. GREBE & CO.



Models AH-1, 160, 1895Q, 225W, 225M

Line Voltage 115—Volume Control Full On

TUBE NO. IN ORDER USED	TYPE OF TUBE	POSITION OF TUBE IN SET	METER READINGS WITH JEWELL TEST PLUG IN SOCKET OF SET — OPERATING VOLTAGES						METER READINGS WITH JEWELL TEST PLUG IN SOCKET OF SET — MILLIAMPERES					
			FILAMENT OR HEATER	PLATE OR ANODE	CONTROL GRID — SEC. + CO+	NORMAL GRID — SEC. + CO+	CATHODE TO HEATER	SCREEN GR TO HEATER	PLATE R.M.30 TO PLATE	TUBE TEST	PLATE CURRENT CHANGE
	224	1 R.F.	2.4	160	2.5	80	-	-	2.5		
	224	2 R.F.	2.4	160	2.5	80	-	-	2.5		
	224	3 R.F.	2.4	160	2.5	80	-	-	2.5		
	227	Det.	2.4	200	-	20	-	-	2.0		
	245	PP-AF	2.4	250	-	14	-	-	50		
	245	PP-AF	2.4	250	-	14	-	-	50		
	280	Rect.	4.8	-	-	-	-	50	50		

Volume Control Minimum

TUBE NO. IN ORDER USED	TYPE OF TUBE	POSITION OF TUBE IN SET	METER READINGS WITH JEWELL TEST PLUG IN SOCKET OF SET — OPERATING VOLTAGES						METER READINGS WITH JEWELL TEST PLUG IN SOCKET OF SET — MILLIAMPERES					
			FILAMENT OR HEATER	PLATE OR ANODE	CONTROL GRID — SEC. + CO+	NORMAL GRID — SEC. + CO+	CATHODE TO HEATER	SCREEN GR TO HEATER	PLATE R.M.30 TO PLATE	TUBE TEST	PLATE CURRENT CHANGE
	224	1 R.F.	2.4	190	15	90	-	-	2.5		
	224	2 R.F.	2.4	190	15	90	-	-	2.5		
	224	3 R.F.	2.4	190	15	90	-	-	2.5		
	227	Det.	2.4	225	-	21	-	-	2.0		
	245	PP-AF	2.4	250	-	14	-	-	50		
	245	PP-AF	2.4	250	-	14	-	-	50		
	280	Rect.	4.8	-	-	-	-	50	50		

Courtesy Nostalgia Air